

PLAN
SCALE 1:20

MULCH TO BE INSTALLED FOR FULL WIDTH OF MEDIAN VERGE WHERE PRACTICABLE

'A' MIX SOIL IN ACCORDANCE WITH NEWCASTLE URBAN FOREST TECHNICAL MANUAL

BARRIER KERB AND GUTTER

OPTIONAL VERTICAL EXCAVATION ONLY WHERE SPACE IS CONSTRAINED

MULCHED WATERING SOIL BERM AT SURFACE AT EDGE OF THE ROOTBALL 100 HIGH x 100 WIDE TYPICAL

BACKFILL KERB WITH GENERAL FILL TO 98% STANDARD COMPACTION TYPICAL


BARRIER KERB AND GUTTER

INDICATIVE ROOTBALL

CROSS SECTION
SCALE 1:20

NOTES



1. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH THE NEWCASTLE URBAN FOREST TECHNICAL MANUAL.
2. BREAK GLAZING IN CLAY SIDES AND BASE OF TREE PIT.
3. IF EXISTING SITE SOIL IS DEEMED INAPPROPRIATE BY A CITY OF NEWCASTLE CITY GREENING OFFICER AND CANNOT BE REMEDIATED, IMPORT 'A' MIX SOIL IN ACCORDANCE WITH NEWCASTLE URBAN FOREST TECHNICAL MANUAL.
4. MIX IN TERRACOTTEM AS PER MANUFACTURERS INSTRUCTION.
5. WATER THE PLANT TO SATURATION DURING BACK FILLING.
6. IF PLANTING IN POOR DRAINING SOIL (EG. CLAY) SUBSOIL DRAINAGE MAY BE REQUIRED. REFER TO STANDARD DRAWING A3008 FOR REQUIREMENTS
7. PROVIDE MAXIMUM 80mm MULCH TO FULL EXTENT OF TREE PIT TO PLAN DIMENSIONS.
8. THIS DRAWING APPLIES TO SPEED ZONES LESS THAN 70km/h



LONG SECTION
SCALE 1:20

SUBSOIL DRAINAGE SHALL BE IN ACCORDANCE WITH CN STANDARD DRAWINGS A2003 AND A3008

TREE PLANTING - STREET MEDIAN TREE

3	REVISION	30/03/23	T.C	SCALE AS SHOWN DO NOT SCALE DRAWING	 <div>City of Newcastle</div>	APPROVED:  SIGNED:..... EXECUTIVE MANGER ASSETS AND FACILITIES 16/06/23 DATE:.....	CITY OF NEWCASTLE STANDARD DRAWING	NCC PLAN No.		SHEET No.
2	REVISION	24/11/22	T.C					A3004		
1	CONSTRUCTION	18/12/14	T.A				TREE PLANTING STREET MEDIAN		OF	
0	PRELIMINARY	18/11/14	T.A						1	
ISSUE	AMENDMENT DETAILS	DATE	INITIALS	REVIEWED	J.C		SHEET A3	ISSUE 3	SHEETS	