



SECTION  
**TURF - SOIL PROFILE AND INSTALLATION DETAILS**  
 SCALE 1:10

**NOTES**

1. FINISH CROSSFALL TO TURF SHALL BE 1:80 MIN. FINISH FLUSH WITH ADJOINING SURFACES.
2. AMELIORATE SITE SOIL OR IMPORT TOPSOIL TO PROVIDE A TURF UNDERLAY THAT COMPLIES WITH AS4419.
3. AMELIORATE CLAY SUBSOIL WITH GYPSUM APPLIED AT THE RATE SPECIFIED BY THE MANUFACTURER. REMOVE CONTAMINATED AREAS, DELETERIOUS MATERIAL SUCH AS LARGE ROCKS GREATER THAN 50mm, RUBBISH AND LARGE TWIGS.
4. LAY TURF PARALLEL TO CONTOUR, CLOSE BUTTED AND LIGHTLY TAMP.
5. FILL JOINTS WITH TOP DRESSING SOIL.
6. PROVIDE SUBSOIL DRAINAGE TO ADDRESS ANY POORLY DRAINED AREAS.
7. WATER IN AND MAINTAIN CONSISTENT DEEP WATERING FOR 14 WEEKS MINIMUM. REDUCE WATERING FREQUENCY CONSISTENTLY DURING THE REMAINDER OF THE PLANTING ESTABLISHMENT PERIOD.
8. CONSISTENTLY TOP DRESS DEPRESSIONS TO PROVIDE AN EVEN SURFACE.
9. MOW, TOP DRESS AND CONTROL PESTS, DISEASE CONSISTENTLY DURING THE PLANTING ESTABLISHMENT PERIOD.
10. ALL TURF ORDERS TO BE SUPPLIED FREE OF PLASTIC REINFORCEMENT MESH.

SCALE <b>AS SHOWN</b>				 LIVEABLE CITY INFRASTRUCTURE MANAGEMENT SERVICES	APPROVED:	<b>THE CITY OF NEWCASTLE</b>	NCC PLAN No.	SHEET No.
1	CONSTRUCTION	18.12.14	T.A.		 SIGNED: ..... INFRASTRUCTURE MANAGEMENT SERVICES MANAGER	<b>TURF</b>	<b>A3100</b>	1
0	PRELIMINARY	18.11.14	T.A.	REVIEWED: J.C.	DATE: 16/11/15	<b>SOIL PROFILE AND INSTALLATION DETAILS</b>	AMENDMENT No.	OF
No.	AMENDMENT DETAILS	DATE	INITIALS					1
A3 ORIGINAL THIS SHEET WAS PREPARED IN COLOUR AND WILL BE INCOMPLETE IF COPIED				COORDINATE SYSTEM:	HEIGHT DATUM: AHD			SHEETS