

# Stockton Beach Coastline Works

December 2023 This information is subject to change.

## Works

- Rockwall
- ▬▬▬▬ Rockbags
- ▬ Buried Seawall
- ▬▬▬▬ Emergency Repair Works
- ▬▬▬▬ Repair Works
- ⚠ Emergency Works
- 📄 Actions from the 2020 CMP

**Corroba Oval area - Dune works**

- Straw bales and coir logs have been used in this area to help trap sand and reduce the impact of wave overtopping. In 2024 additional straw bales will be placed, along with planting to stabilise the dune area.
- Sand scraping is regularly undertaken in this area to increase dune height.

**Barrie Crescent - Rockbags**

- 1,294 Kyowa rockbags were placed along this 210-metre section of coastline in 2021.

**Mitchell Street - Rock seawall**

- The seawall was built in 1991, and covers 600m of coastline.
- Planning is underway to increase protection following construction of the new buried structure at the southern end.
- In advance of this, rock bags have been placed on top of the seawall at the northern end of Mitchell Street to minimise the risk of overtopping until the seawall works are complete.

**Southern end of the Mitchell Street seawall  
New buried seawall**

- The sandbags and rockbags at the southern end of the Mitchell Street seawall have been removed to allow for construction of a permanent buried protection structure. Work on the new structure started in September 2023 and is scheduled for completion in mid-2024.

**The Pines - Emergency repair works**

- Weather events have exposed historic building materials which were put in place in the 1970's to minimise erosion. We have undertaken temporary works to protect the dune edge, including relocating fencing in this area to ensure community safety.
- We are currently developing plans for longer-term protection of the beach frontage.

**North of Stockton Surf Lifesaving Club**

- Repair work has taken place on the existing emergency works, which will be monitored on an ongoing basis, ahead of construction of a new structure. Design of this new structure is being assessed in line with adjacent works planned at The Pines.

**Stockton Surf Lifesaving Club - Rock seawall**

- The seawall in front of the SLSC was built in 2017 following significant erosion.
- We are currently planning longer term repairs to the seawall with construction planned in 2024 following the repairs to the Mitchell Street seawall.

**Front of Lexie's Café**

- Emergency sandbags are located on the seaward side of Lexie's Cafe.
- A new structure to protect the area until mass sand nourishment is delivered will be designed to integrate into adjacent works.
- Until this structure is delivered we will continue to monitor and renew the existing sandbags as needed.

**Sand scraping**

- When weather allows, we undertake sand scraping activities in areas like this to increase dune resilience by accelerating the natural movement of sand.

**Stockton breakwater - Repair works**

- We have now completed work to repair damage from erosion events and reinstate access for the community including a new accessway to South Stockton Beach. Work will commence on revegetation of the site and improved pedestrian access in early 2024.

